



Keeping the Lights On:

Energy Facility Flood Mitigation Projects in New England – Takeaways for Protecting Critical Assets and Infrastructure

Proactive By Design.
Our Company Commitment



Presented by: Gary McAllister, P.E.
Jennifer Burke, P.E.



Topics



- Background
- Flood Resilience Options
- GZA's Work
 - Permanent Flood Control Solutions
 - Temporary and Mobilized Solutions
 - Testing
- Conclusions/Takeaways



Background



- Climate change/sea level rise/larger events
- Super Storm Sandy
 - 8.1M homes without power in 17 states
 - 57k utility workers assist in returning power to NYC
- Post-Super Storm Sandy Lessons
 - Restoring power can be:



**Time
consuming**



Costly



**A public relations
nightmare**



Flood Risk Mitigation – Substation Specific Issues




- Security
- Safety
- Accessibility and Space Limitations
- Underground Penetrations

Plus typical issues:

- Cost
- Maintenance
- Schedule
- Compatibility with future projects
- Site constraints
- Permitting – comp. storage
- Risks/benefits
- Adaptability to climate change



Protecting Critical Infrastructure





Flood Resilience Options



- Physical Options
 - No Flooding
 - Controlled Flooding
- What gets protected?
- Longevity of Solution
 - Long-term
 - Interim
 - Mobilized



Floodwall protects Our Lady of Lourdes Hospital in Binghamton, NY along Susquehanna River in 2011 during Tropical Storm Lee



Flood Resilience - Option 1 No Flooding

GEOTECHNICAL

ENVIRONMENTAL

ECOLOGICAL

WATER

CONSTRUCTION
MANAGEMENT



Permanent Barrier



Re-Build above DFE



Mobilized Barrier

Interim Barrier






Flood Resilience - Option 2 Controlled Flooding



**Raise Panels /
Equipment**



Dry Floodproofing





Permanent Flood Control Barriers

GEOTECHNICAL

ENVIRONMENTAL

ECOLOGICAL

WATER

CONSTRUCTION
MANAGEMENT



Steel Sheet Pile



Concrete



Vinyl Sheet Pile



Fiberglass Sheet Pile



Interim Flood Control Barriers

GEOTECHNICAL

ENVIRONMENTAL


ECOLOGICAL

WATER

CONSTRUCTION
MANAGEMENT




Sand Bag (Big Bag)



Timber Wall



Reinforced Barrier (HESCO)



Shaped Bag (Trap Bag)



Mobilized Flood Control Barriers

GEOTECHNICAL

ENVIRONMENTAL

ECOLOGICAL

WATER

CONSTRUCTION
MANAGEMENT



Aquafence




Invisible Wall



Floodstop



Sand Bag



Bladder Dam



Flood Control Barriers Control of Water




Duck bill




Flap gates

Interior Sump & Pump



Exterior Sumps & Pumps





Project Overview



- Permanent flood control concepts
 - 11 substations in New England
 - Design Flood Elevation (DFE)
 - Set based on ASCE-24
 - Base Flood Elevation (BFE) +2 (or +3)
- Interim flood control concepts
 - 22 substations in New England
 - Flood Contingency Plans (FCPs)
 - Temporary controls (2-3 years)
 - Mobilized controls



Permanent Flood Control Concept Plans

GEOTECHNICAL

ENVIRONMENTAL


ECOLOGICAL

WATER

CONSTRUCTION MANAGEMENT



FEMA Flood Zone Boundaries





Permanent Concepts – Site Specific Realities

GEOTECHNICAL

ENVIRONMENTAL

ECOLOGICAL

WATER

CONSTRUCTION
MANAGEMENT



Property constraints



Aging seawall



**Historical
structures,
tunnels/conduits**

Page | 16



Flood Control Concept Selection Process



“The Results”

	Engineering/Installation / Construction		Risk/Opportunity		Operations, Maintenance, & Replacement Cost (thousands)
	Capital Cost (thousands)	Critical Path Duration (months)	Weighted Risk	Weighted Opportunity	Flood System Design Life= 50 years
Alternative 1 – Floodwall around Existing 23kV Yard and Building Housing 4kV yard, Flood-proofing north wall of building.	\$3,824	40.0	19.0	11.0	\$640
Alternative 2 – Construct new raised 23kV yard, decommission existing 23kV yard, Allow building to flood	\$3,379	51.5	15.0	9.0	\$55
Alternative 3 – Floodwall around 23kV yard ONLY, Allow building to flood	\$2,503	36.5	10.0	1.0	\$565



Flood Contingency Plans/ Mobilized Concepts


GEOTECHNICAL

ENVIRONMENTAL

ECOLOGICAL


WATER

CONSTRUCTION
MANAGEMENT






Flood Contingency Plans/ Mobilized Concepts Testing



Geotextile between cells

Geotextile not folded under

Mock-Up #1 HESCO Testing



End dumped fill



Flood Contingency Plans/ Mobilized Concepts Testing



Mock-Up #1 HESCO Testing




Excessive Internal Seepage



Increasing Flow, Piping




Flood Contingency Plans/ Mobilized Concepts Testing



Mock-Up #1 HESCO Testing



Loss of Strength – Potential
Failure of Multiple Cells



Loss of Fill – Imminent Failure
of Cell



Flood Contingency Plans/ Mobilized Concepts Testing

GEOTECHNICAL

ENVIRONMENTAL

ECOLOGICAL

WATER

CONSTRUCTION
MANAGEMENT



Mock-Up #2 HESCO Testing

Geotextile folded under this time

Geotextile damage due to
compaction method





Conclusions/Takeaways



1. Need to listen and understand Client needs
 - Facility – past, present, and future
 - Operations and capabilities
 - What needs protection?
2. Thorough design development is key
3. Proper installation, training, and execution are essential



Contact Info



Gary McAllister, P.E.
GZA GeoEnvironmental, Inc.
477 Congress St., Suite 700
Portland, ME 04101
(207) 879-9190
gary.mcallister@gza.com

Jennifer Burke, P.E.
GZA GeoEnvironmental, Inc.
1350 Main Street, Suite 1400
Springfield, MA 01103
(413) 726-2100
jennifer.burke@gza.com