

#### When Neighbors Say No: Navigating Complex Property Owner Relationships




**COMMITMENT & INTEGRITY DRIVE RESULTS** 



## Waterway projects within multiple jurisdictions are commonplace

**Runnins River at Warren Ave:** 








#### Runnins River defines the RI/MA state line


- 7.5 miles long
- 10 square mile watershed
  - ➢ 70% in Seekonk, MA
  - ➢ 23% in East Providence, RI
  - ➢ 7% in Rehoboth, MA







Increase in frequency of flood incidents over the past 40 years in this East Providence, RI neighborhood prompted mitigating actions.







#### Past Studies recommended replacing the Warren Avenue Bridge to increase the effective flow area

- 1986 Warren Avenue Drainage Study
- 2007 Runnins River Drainage Study











#### **East Providence Takes Action**


- 1. Secured a CDBG Disaster Recovery Grant for \$500,000.
- 2. Requested Design-Build proposals for construction of two 60-inch high relief culverts adjacent to the Warren Avenue Bridge.
- **3.** J.H. Lynch & Sons, Inc. was the successful bidder and was awarded the contract in November 2015.




# Alternative Design Options Developed










#### Easements then become the primary driver

 RIDOT required a temporary construction easement and a perpetual maintenance easement

> AND

The selected option required easements from four private property owners


Easement pursuit begins in December 2016




## WOODARD

## By June 2017 one opposing property owner forces Option 4

- An East Providence property owner would not allow a temporary construction easement.
- The potential loss of business from the 30-day bridge closure could not be overcome by property improvements or sale of a portion of that property to the City.






### The BWRF rescues the project

- Rhode Island's Narragansett Bay and Watershed Restoration Fund (BWRF) added a new Flood Prevention and Mitigation Sub-fund in 2017.
- The project was eligible because it mitigates flooding problems in Rhode Island.
- East Providence applied for and received a \$544,025 grant.




#### Design proceeds with two new culverts in Massachusetts





#### Hydrologic/Hydraulic Modeling


- Plans of Record
- Peak flow rates developed using RI and MA GIS
- HEC-RAS Model
- Supplemental Dynamic H/H Model
- Findings
  - Significant drop in water elevation upstream (objective of the Project)
  - > No adverse impact downstream
  - > A FEMA No-Rise Certificate was required





#### **Design Considerations**


- Base Flow / Low Flow
- Existing RIDOT Arch Culvert
- Existing Utilities
- Town Drainage System Connections
- Future RIDOT / Town of Seekonk Projects
- MassDOT Small Bridge Criteria





#### **Geotechnical Design**

- Structural Stability of Existing Arch Culvert
- Poor Subgrade Conditions
- Dewatering
- River Bypass
- Accelerated Construction Techniques





#### Permits were received from:


- RI Department of Transportation:
  - Physical Alteration Permit
  - ➢ Traffic Management Plan
- Massachusetts Department of Transportation:
  - ➢ Traffic Management Plan
- Seekonk Conservation Commission:
  - Order of Conditions
- Army Corps of Engineers:
  - General Permit 10 for Linear Transportation Projects and Stream Crossings






#### Construction was ready to proceed in July 2018

- Temporary easements for construction
- The schedule met the MA
  Division of Marine Fisheries
  Time of Year restrictions
- Notifications were sent to all stakeholders two weeks in advance





#### The Town of Seekonk realized construction was imminent.


- The road opening permit was withheld until:
  - > A second peer review was performed on the river hydraulics;
  - The culvert design was revised to separate the two new culverts by 2+ feet to avoid classification by Mass DOT as a BRI bridge;
  - The Seekonk Conservation Commission approved the modified design with the culvert separation; and
  - Miscellaneous additional amenities to County Street were incorporated into the project.



#### Two months later

- The Division of Marine Fisheries approved the work within the fall time of year restriction.
- Heavy rains throughout September and October 2018 foretold problematic construction.
- The team decided to delay construction to July 2019.

DESIGN	PERMITTING	REDESIGN	PERMITTING	TOY RESTRICTION	
November 2015 Project Award				July 20 Construction St	








#### Construction









The Project removed 25 homes from a 100-year flood area



The Project removed 30 homes from a 10-year flood area





#### Key project take-way:

### Communicate early in the project and aggressively seek responses from all stakeholders

- Early easement negotiations with the property owners would have confirmed the Massachusetts location before design began and avoided:
  - RIDEM permitting
  - Permit modifications
  - Preparation of an Environmental Assessment
  - CDBG time extensions
- A visit to the Seekonk DPW could have prompted the director to perform a detailed project review months earlier, thus avoiding the one-year construction delay.
- A pre-application meeting with the RIDEM grant administrator contributed to the BWRF grant award.



### **Questions?**



#### Jan Greenwood, P.E.

jgreenwood@woodardcurran.com



#### Paul Jacques, P.E. pjacques@woodardcurran.com

COMMITMENT & INTEGRITY DRIVE RESULTS